

materiali

Specifikācija
materiāli

Dienvidkurzemes novads,
Grobiņa (Dienvidi)

n.p.k.	Nosaukums	mērv.	Daudz.	Piezīmes
1	caurule d25	m	197	
2	caurule d40	m	755	
3	caurule d50	m	27	
4	kamera 300x300x300	gab.	74	
5	kamera 812x540	gab.	7	
6	kamera 614x230	gab.	2	
7	Betona riņķis + čuguna vāks kamerai 812x540	gab.	1	
8	Divpusēja aizsargcaurule 750N d-110	m	52	
9	Divpusēja aizsargcaurule 750N d-160	m	22	
10	FO Cable 4F	m	8778	TKF / CTC 4xSM G.657A1 / Parameters see in products attachment
11	FO Cable 12F	m	949	TKF / CTC 12xSM G.657A1 / Parameters see in products attachment
12	FO Cable 24F	m	3380	TKF / CTC 24xSM G.657A1 / Parameters see in products attachment
13	Uzmava SubMag. BPEO-S0	pcs.	8	CORNING / 3M BPEO-S0 / Parameters see in products attachment
14	Optiskā kasete, uzmaiņai	pcs.	17	CORNING K7 Splice Cassette 2 Slot, Uni Zone-12 / FQ100068284
15	Double-Entry Cable Sealing 4,5-6mm	pcs.	1	CORNING ECAM D18 Main Body / FQ100084638
16	Sealing for mid-span access 4,5-6mm	pcs.	1	CORNING ECAM D18 Main Body / FQ100084646
17	Single-Entry Cable Sealing 3,5-9mm	pcs.	46	CORNING ECAM S9.5 ROUND / UU003028675
18	Uzmava Abon. OSC-12	pcs.	6	CORNING / OSC-12 / Parameters see in products attachment
19	FO Box 24SC	pcs.	1	FO terminal Box 24F / HTTP-001
20	Fusion splice procector 40/2,5mm, uzmaiņai	pcs.	13 (1300pcs)	OPTON / OP-SP2545
21	Optical Splitter 1x32	pcs.	1	OPTON / OP-PLC-1X32-AB-SCA-1/ Symmetric splitter PLC 1x32 ABS box SM 2mm 1m SC/APC
22	Street Box RSZ-140/44/20, complete	pcs.	11	MANTAR / RSZ-140/44/20 72SC
23	Pigtail SC/APC 1,5m	pcs.	578	OPTON / pigtail SC/APC SM 0.9mm 1.5m G657A Loose Tube (Easy Strip) / OPIG-657A-SCA-1.5-LT

darbi

Specifikācija
veicamie darbi.

Dienvidkurzemes novads,
Grobiņa (Dienvidi)

n.p.k.	Nosaukums	mērv.	Daudz.
1	cauruļu ieguldīšana guntī atklātā veidā d50	m	27
2	cauruļu ieguldīšana ar caurdures metodi d40	m	720
3	cauruļu ieguldīšana guntī atklātā veidā d40	m	35
4	cauruļu ieguldīšana ar caurdures metodi d25	m	64
5	cauruļu ieguldīšana gruntī atklātā veidā d25	m	133
6	kameras 812x540 uzstādīšana	gab.	6
7	kameras 812x540, betona rīņķi, čuguna vāks uzstādīšana	gab.	1
8	kameras 614x230 uzstādīšana	gab.	2
9	kameras 300x300x300 uzstādīšana	gab.	74
10	kabeļu instalācija esošās komunikācijās 4F	m	8778
11	kabeļu instalācija esošās komunikācijās 12F	m	949
12	kabeļu instalācija esošās komunikācijās 24F	m	3380
13	Uzmava SubMag. BPEO-S0 uzstādīšana	gab.	8
14	Uzmava Abon. OSC-12 uzstādīšana	gab.	6
15	FO Box 24SC uzstādīšana	gab.	1
16	Street Box RSZ-140/44/20, complete uzstādīšana	gab.	11

caurdures: 784 m
rāviņa: 195 m

